

DEMOLITION FLOOR PLAN

1/4"=1'-0"

A

NOT USED

DEMOLITION GENERAL NOTES

KEY NOTES

1. VERIFY ALL CONDITIONS PRIOR TO DEMOLITION. DISCREPANCIES BETWEEN DESIGN AND EXISTING CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE NPC PROJECT MANAGER.
2. PATCH AND REPAIR FLOOR AND WALLS THAT ARE DAMAGED IN THE PROCESS OF DEMOLITION.
3. REMOVE ALL ABANDONED CONDUIT, PIPING, HVAC DUCT, LIGHTING, OUTLETS AND EQUIPMENT.
4. REFER TO PROJECT GENERAL NOTES ON SHEET T1.

1. EXISTING DOOR TO REMAIN.
2. EXISTING WINDOWS TO REMAIN.
3. EXISTING WALLS TO REMAIN.
4. REMOVE EXISTING WATER CLOSET, LAVATORY AND RESTROOM EQUIPMENT
5. REMOVE EXISTING WALL.
6. REMOVE EXISTING DOOR.
7. REMOVE EXISTING EQUIPMENT AND ASSOCIATED MECHANICAL, PLUMBING AND ELECTRICAL.
8. PREPARE SLAB TO RECEIVE NEW PORCELAIN TILE (FT-1) & BASE AS SCHEDULED. (SEE A3 - FINISH SCHEDULE). (REFER TO SHT. A1 FOR EXACT LOCATION).
9. PREPARE SLAB TO RECEIVE NEW PORCELAIN TILE (FT-2) & BASE AS SCHEDULED. (SEE A3 - FINISH SCHEDULE). (REFER TO SHT. A1 FOR EXACT LOCATION).
10. NOT USED.


11. REPLACE EXIST. GYP. BD. @ BOTTOM OF WALL WITH NEW CEMENTIOUS BOARD. REFER TO 1 & 2/A8 FOR HT. OF NEW CEMENTIOUS BOARD FROM FLOOR.  
  
VERIFY REPLACEMENT OF EXIST. GYP. BD. @ BOTTOM OF EXISTING DEMISED PARTITIONS WITH FIRE MARSHAL BEFORE REMOVAL.  
  
MAINTAIN EXISTING RATING OF DEMISED PARTITIONS.
12. REMOVE EXISTING SUSPENDED CEILING GRID AND PLYWOOD ABOVE. PREP FOR NEW SUSPENDED CEILING.


DATE: 12.15.2023  
JOB NO: 4521  
DRAWN: FS  
CHECKED: DL

DEMOLITION  
FLOOR PLAN

  
FRANCHISEE  
HUT CENTRAL VIRGINIA, LLC  
6200 OAK TREE BLVD  
STE 250  
INDEPENDENCE, OH 44131

PIZZA HUT #4521  
1344 SOUTH MAIN STREET  
SUITE 3  
BLACKSBURG, VIRGINIA

  
14 West 3rd Street, Suite 100  
Kansas City, MO 64105  
(P) 816.421.8927  
(F) 816.421.8926

  
DANIEL A. LICKEL  
NO. 16201  
ARCHITECT  
12.15.2023

SHEET NUMBER  
DM1

REVISIONS: